SANITARY CIRCLE.

Notice, dated 29th November 1895.

Tenders are hereby invited up to 20th December 1895 for completing the roads in the Western extention, Bangalore City.

2. Further particulars and conditions may be seen at the Assistant Engineer's office, B. C. W. D. Range, the Fort, Bangalore between the hours of 11 A. M. and 4 P. M. daily.

3. The final acceptance of any tender will rest with the Sanitary Engineer with the Government of Mysore, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

4. No tender will be received unless accompanied by a deposit of Rs. 100 as earnest money.

5. Within eight days of the acceptance of the tender, the contractor will be required to deposit Rs. 150 as security and to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

6. The name of the contractor, whose tender has been accepted, will be posted on the notice board in the Assistant Engineer's office, Fort, Bangalore in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

8. An approximate estimate in quantities of items of work required are given below. These quantities are not guaranteed.

Items of work.	*Per.*	*Quantity.*
Embankment (lead 100 feet)	C. yds.	44,428
Cutting	,,	16,983
Sectioning and forming	S. yds.	152,476
Metalling (Jungle)	C. yds.	2,339
Gravelling	,,	3,034
Sanding	,,	262
Earth side drains	,,	5,058
Gravelling slopes	Sqrs.	1,344·44
Blasting rock	C. yds.	2,614
Earthwork, excavation	,,	2,335
Burnt stone in chunam	C. ft.	4,920
Do in clay	,,	27,000
Do covering slabs	S. ft.	9,966
Do slabs for flooring and cross drains	,,	14,520
Chunam pointing	Sqrs.	107·80
Rough stone work for apron and flooring	C. yds.	7$\frac{1}{8}$
Earth filling over slabs	,,	248
Mud wall	R. yds.	200
Coping (burnt brick in clay including chunam plastering) ..	R. ft.	600
Mud plastering	Sqrs.	60·00
White-washing	,,	78·00

O. V. NORRIS, *Asstt. Engineer, B. C. W. D. Range.*

BANGALORE CITY MUNICIPALITY.

The 7th December 1895.

The following business will be transacted at the ordinary meeting of the Municipal Commissioners for the City of Bangalore to be held at their office premises at 8 A. M. on Friday the 20th December 1895.

1. Cash Account Current, Mortuary Return, Itinerant Medical Officer's Return, Demand, Collection and Balance Statement, Progress Report of Works, the Memo of Visitors to the Srinivas Mandiram Library, City Municipal English and Kanarese School Returns, Return of Cases attended by Midwives, Abstract of Lighting Report, Maternity Return and Statement of Materials for November 1895.

2. Docket No. 727, dated 25th October 1895, from the Assistant Engineer, B. C. W. D. Range, *in re* transfer of the conservancy establishment working on the Distillery tank feeding channel to the management of the Municipality.

3. Nomination of Sub-Committee to consider the works to be entered in the Budget for the ensuing year 1896-97.

K. SRINIVASA ROW, *Vice-President.*